

Addendum 3

Issued May 12, 2026

The following information changes the competitive process documents issued on April 10, 2026.

GENERAL INFORMATION

Item 1: See 'Addendum 2' dated May 12, 2026 issued by the Gacesa Slote Architects Inc. (2 pages)

End of Addendum 3

TENDER ADDENDUM NO. 2

2026.05.12

Norwood Park Elementary School Accessibility Project
Hamilton Wentworth District School Board RFT-2026-119-P02267
165 Terrace Drive, Hamilton, Ontario

The following information supplements and/or supersedes the Tender documents. This Addendum forms part of the contract documents and is to be read, interpreted, and co-ordinated with all other parts. The cost of all contained herein is to be included in the contract sum. The following revisions supersede the information contained in the original drawings and specifications issued for the above-named project to the extent referenced and shall become part thereof. Acknowledge receipt of this Addendum by inserting its number and date on the Tender Form. Failure to do so may subject the Bidder to disqualification.

2.1 Mechanical Addendum No. 1:

1. Refer to attached Mechanical Addendum No. 1 dated May 11, 2026, for revisions to Mechanical drawings and specifications (1 page total).

2.2 Questions & Answers not addressed above:

- Q1 Drawing A2.0 – Room 211 has demo note D5 to remove all flooring and base, what is the spec for the new flooring?
- R1 Classroom 211 to receive VCT flooring and rubber base as noted in the Room Finish Schedule included in the Project Manual.**
- Q2 Key Notes 7 new wall tile CT-C does this get installed on the wall of room 203 that is bubbled?
- R2 No new wall tile in Classroom 203. For type and extent of wall tile in B.F. Washroom 203A, refer to HWDSB Addendum #2 and to drawings and room finish schedule.**
- Q3 Is there any make good flooring in the corridors, is so what is it?
- R3 Yes, as per keynote 8, provide terrazzo floor and base patching and also at door D211.**

END OF ADDENDUM NO. 2



CoPA ENGINEERING LTD.

29 Rolling Acres Drive, Kitchener, Ontario N2A 3W5

Mob:(519) 496-2672
E-mail:copaeng@gmail.com

Interior Renovations for HWDSB Norwood Park
Accessibility Upgrades
165 Terrace Drive, Hamilton

MECHANICAL ADDENDUM No.1 - May 11, 2026

THIS ADDENDUM SHALL BE READ WITH AND CONSTITUTES PART OF THE TENDER DOCUMENT

1. Drawing M3-1, Mechanical General Requirements and Installation Notes
Incorporate the Building Automation Controls (BAS).
 - .1 The Building Automation Controls supply and installation shall be undertaken by the current HVAC Controls contractor responsible for the building automation controls.
 - .2 Contact Jake Rendulic at Siemens Canada Ltd., email:jake.rendulic@siemens.com
 - .3. The building automation controls supply and installation shall be included in the base bid and indicated as a separate price. Confirm controls company to be used.
 - .4 Relocate thermostat and control components serving existing classroom..
 - .5 Update graphics to incorporate
 - new elevator pit sump pump for "Status" and "Alarm". The sump alarm panel will be located in the elevator machine room.
 - elevator machine room transfer fan TF1 "Status" and "Alarm". Supply and install reverse acting thermostat for TF1.

END OF ADDENDUM

Issued by: Costas Pashartis, P.Eng.