Hamilton

Date Issued: November 2, 2026

C13-25-26 - General Contractor for Hamilton Stadium Artificial Turf Replacement Project

ADDENDUM 2

---

1. REVISION

1. Section 02 90 00, Artificial Turf Surfacing, Part – 1 General

Add: 1.10 APPROVED INSTALLER QUALIFICATIONS

.1 **Experience:** The approved installer shall be a pre-approved from the acceptable artificial turf systems (or approved equivalent).

a. The approved installer shall have achieved FIFA Quality Pro (or its predecessor FIFA 2 Star) field certification, or passed an accredited FIFA Quality Pro field test, at completion in a cold climate.
b. The approved installer shall have completed full-size turf replacements over a retained shock pad, where the existing turf and infill were removed.

.2 **On-site lead:** The Successful Bidder must ensure the approved installer's lead shall be on site full-time during all turf work and shall not be changed without the City's written approval. The acceptable artificial turf systems (or approved equivalent) shall be installed by the named approved installer's own crew.

.3 **Approval:** The Successful Bidder must seek approval from the City prior to making any changes to the approved installer or acceptable artificial turf systems (or approved equivalent). No changes to the approved installer or acceptable artificial turf systems (or approved equivalent) are permitted without the City's written approval.

Based on a review of the approved acceptable artificial turf systems (or approved equivalent), the City will issue an addendum to notify the Bidders of the approved installers. The Successful Bidder must have the approved installers install the acceptable artificial turf systems (or approved equivalent)"

2. Bidding System, Schedule of Prices,

Revisions have been made and updated in the Schedule of Prices within the Bidding System for the following item:

- **Bidders Acceptable Artificial Turf Systems (or Approved Equivalent) Confirmation**

Bidders must include the acceptable artificial turf systems (or approved equivalent) at time of closing:

2. BIDDER QUESTIONS AND CITY RESPONSES

Q5: As well re project completion: on page 88 of the file, it states substantial completion by April 1, 2027. Are you estimating that turf field can be installed in Hamilton in March? Please advise if this is correct or do you mean April 30.

R5: Acceptable artificial turf systems (or approved equivalent) must be installed before the substantial completion date of April 1, 2027.

Q6: Please clarify whether the existing concrete footing for the football goal post should be replaced with a new concrete footing.

R6: The existing concrete goal post footings are to remain in place. New concrete footings are required at the revised goal post locations to accommodate the updated CFL dimensions, as shown on the drawings EX-1, and L1 supported by the Lump Sum Breakdown of Base Bid Price, Item B.1 that requires supply and install two (2) new concrete footings.

END OF ADDENDUM